



MIXED METAL OXIDE ELGARD 210 ANODE MESH

REVISION 1

ELGARD™ Anode mesh is composed of a precious metal oxide catalyst sintered to an expanded Titanium mesh substrate. The Anode Mesh is used as a key component in the Cathodic Protection of Reinforced Concrete Structures.

MATERIAL SPECIFICATIONS

ANODE PERFORMANCE	
Current rating @ 110 mA/m ² (10 mA/ft ²)	24.4 mA/m ² (2.22 mA/ft ²)
Expected life (NACE Standard TM02944-94)	75 Years
Catalyst	Iridium Based Mixed Metal Oxide
Maximum anode concrete interface current density :	
FHWA limit	110 mA/m ² (10 mA/ft ²)
Short-term limit	220 mA/m ² (20 mA/ft ²)
NOMINAL DIMENSIONS	
Width of roll	1.22 m (4 ft)
Length of roll	76 m (250 ft)
Area per roll	92.9 m ² (1000 ft ²)
Actual anode surface per unit area of concrete	0.22 m ² /m ² (0.22 ft ² /ft ²)
Expanded thickness	1.981 mm (0.078")
Diamond dimensions	34 x 76 x 0.89 mm (1.33 " x 3.0 " x 0.035 ")
Shipping weight per coil	33kg (73 lbs)
SUBSTRATE	
Composition	Titanium, Grade 1 per ASTM B265
Coefficient of thermal expansion	8.7 x 10 ⁻⁵ /°K (0.0000048/in/in/°K)
Thermal conductivity @ 20°C	15.6W/ m ² - °K (9.0BTU/hr/ft ² /°F/ft)
Electrical resistivity	0.000056 Ohm-cm (0.000022 Ohm-in)
Modulus of elasticity	105 GPa (14,900,000 PSI) minimum
Tensile strength	245 MPa (35,000 PSI) minimum
Yield strength	175 MPa (25,000 PSI) minimum
Elongation	24% minimum
ELECTRICAL PROPERTIES	
Anode mesh resistance lengthwise	0.046 Ohm/m (0.014 Ohm/ft)
Current distributor resistance lengthwise	0.049 Ohm/m (0.015 Ohm/ft)
Resistance widthwise c/w current distributor	0.016 Ohm/m (0.005 Ohm/ft)