

[illegible]

Technical cross-section diagram of a road layout. The diagram shows a sidewalk with a person walking, a 2% slope, and a drainage system labeled "Drainage" and "SF". Dimensions are given as 3 and 6. A building is on the right, and a street lamp is on the left. A green dashed line indicates a sight line labeled "VIS 6".

[illegible]

40mm
80mm

230mm

730mm

SLITELAG, Ab 11, 40 mm
BINDLAG, Agb 16, 40 mm
AVRETTING 0-30
BÆRELAG, FK 22-63, 150mm

FORSTERKNINGS-
LAG,
KULT 20-120, 500mm

FIBERDUK KLASSE 4
FORUTSETTER T4-MASSER

40mm
80mm
180mm
680mm

SLITELAG, Agb 11, 40 mm
BINDLAG, Agb 16, 40 mm
AVRETTING 0-30
BÆRELAG, FK 22-63, 100mm

FORSTERKNINGSLAG,
KULT 20-120, 500mm

FIBERDUK KLASSE 4
FORUTSETER T4-MASSER

Technical drawing of a roof construction cross-section. The drawing shows a series of layers with their respective thicknesses indicated on the left and their material specifications on the right. The layers are:

- SLITELAG, Agb 11, 40 mm**: A solid grey layer, 40 mm thick.
- BINDLAG, Agb 16, 40 mm**: A hatched layer, 40 mm thick.
- BÆRELAG FK 0-32, 70 mm**: A layer with small circles representing gravel, 70 mm thick.
- DRENSLAG, var. tykkelse, min. 50 mm FK 16-32**: A layer with small circles representing gravel, with a variable thickness of at least 50 mm.
- FIBERDUK Klasse 2**: A thin layer with a cross-hatch pattern.
- ISOLASJON, Trykkssterk XPS 100 mm**: A thick, solid white layer representing insulation.
- MEMBRAN**: A thin, solid black layer.
- BÆREKONSTRUKSJON**: The structural base, shown as a thick, solid grey layer at the bottom.

On the left, a vertical scale indicates thicknesses of 40mm, 80mm, 150mm, and 200mm. A red dashed line labeled "GRENSESNITT VEGRIB" (cut line) is positioned between the drainage layer and the insulation layer.

smågatestein

gress

fylles i de store fugene
ca 10mm under topp gatestein
etter sammensynking

1/1 steinbredde

100mm

150mm

200mm

Subbus mellom steinene, Fk 0- 4

Settesand, 4-8 mm

DRENSLAG, var. tykkelse, min. 50 mm FK 16-32
FIBERDUK Klasse 2

ISOLASJON, Trykksterk XPS 100 mm

MEMBRAN

BÆREKONSTRUKSJON

GRENSESITT VEGRIS

Diagram illustrating the cross-section of a roof construction, showing the following layers and their dimensions:

- SLITELAG, Ab 11, 40 mm
- BINDLAG, Agb 16, 40 mm
- BÆRELAG FK 0-32, 70 mm
- DRENSLAG, var. tykkelse, min. 50 mm FK 16-32
- FIBERDUK Klasse 2
- ISOLASJON, Trykksterk XPS 100 mm
- MEMBRAN
- BÆREKONSTRUKSJON

Dimensions indicated on the left side of the diagram:

- 40mm
- 80mm
- 150mm
- 200mm

A red line indicates the **GRÆNSESNITT LINJE** (Boundary line).

VARSELINDIKATOR

0.3

0.3

25-35mm
20-30mm

10mm

OPPMERKSOMHETSINDIKATOR

0.3

0.3

10,5 cm

FINHUGGET GRAD 1 KANTSTEIN I GRANITT

VIS 13

BAKSTØP AV JORDFUKTIGT BETONG B35

BAKSTØP 1/3 AV STEINHØYDEN

ARMERING 2 STK Ø8 ARMERINGSJERN

12,5 cm

FUNDAMENT AV SETTESAND

FORSTØP AV JORDFUKTIGT BETONG B35

BAKSTØP 1/3 AV STEINHØYDEN

MERKNADER
KANTSTEIN AV NATURLIGTILFREDSTILLE KRAV
NS 3420 OG NS-EN 1343

MERKNADER
KANTSTEIN AV NATURSTEIN SKAL
TILFREDSSTILLE KRAVENE I
D NS 3420 OG NS-EN 1343
KANTSTEIN SKAL HA FARGE LYS GRÅ.
VALØRFORSKJELL MELLOM KANSTEIN
OG ASFALT SKAL VÆRE MIN 40%

Tegningsnummer:		Revision:	
TF		A-01	
A-01	Anbudstegning	28.08.20	NB
Rev.	Tekst:	Rev.dato:	Tegn./Kont:

Prosjekt: Grilstad Marina B3 Fullriggervegen Oppdragsnavn: Grilstad Marina AS		
Normalprofil Overbygning Kantsteinsdetaljer		
Oppdragsleder: NL Oppdragsnr.: 620856-02	Koordinatssystem: EUREF89 UTM32 Heydedatum: NN2000	Målestokk: 1:100 Arkiformat: A1
Tegn. nr. TF Fsg. Type 101	Rev. A-01	