

Architectural floor plan of a kitchen and dining area. The plan shows a kitchen with a sink, stove, and refrigerator, and a dining area with a table and chairs. Dimensions are provided in meters. The kitchen area is 3.60m wide and 3.20m deep. The dining area is 1.20m wide and 1.50m deep. The total area is 69.0 m². The plan is labeled 'Oppriss 1:20' and 'Kjøkkenøy m/koketø'. A scale bar indicates 1:50.

Oppriss 1:50
Benkerad + høyskap + sitteareal

Langs vegg:
4x Kjøl/Frys kombiskap
1x Frysenskap
1x Kjøleskap
2x Høyskap med 2x Stekeovn og 1x Mikrobølgeovn
1x Vask - stor kum viktigere enn to små eller utslagsvask
2x Underskap under vask for vaskebøtter og kluter
2x Oppvaskmaskin
2x Underskap for søppel med skuff over for bestikk
4x Overskap for servise til 30stk
Bardisk med barstoler og plass til kaffemaskin nært vask
Benkeplater: Ask evt. Hvitpigmentert eil
Skapstammer: Lakkert høytrykkslaminat

Kjøkkenøy:
Innfelt koke topp med stor nok kokeflate til store kjeler
Tørreskuffer, 32stk - 2stk per 40cm bred modul BxHxD 40x40x60



Technical drawing of a kitchen unit. The drawing shows a side view of a cabinet with a door and a handle. The width of the cabinet is indicated as 320. The height of the cabinet is indicated as 600. A red dot is marked on the right side of the cabinet, with a red line pointing to it from the text "Fästning, spritt stål" (Fastening, drilled steel).

Snitt 1:20