



COWI AS							BØYELISTE				Side	1				
							Tilt.haver: Kristiansand Kommune				Oppdr.nr.				A242976	
							Oppdrag: Odderøya Barnehage				Tegn.				200	
							Utført TFR			Dato : 22.04.2022		Kontr. TCSV		Siste rev.		
KONST. -DEL	POS	NR	STÅL KVAL	DIAM. mm	ANTALL stk	KAPPL. mm	Samlet (m²)	m					ANM.	REV.		
Fundamenter		10	B500C	12	6	12000	72									
		11	B500C	12	57	2430	139									
		12	B500C	12	13	1960	25									
		13	B500C				0	0								
		14	B500C				0	0								
		15	B500C				0	0								
		16	B500C				0	0								
		17	B500C				0	0								
		18	B500C				0	0								
		19	B500C				0	0								
Samlet armeringsmengde denne side							Akkumulert side 1 tom. denne side									
Diam.		Sum meter			Sum kg		Diam.		Sum kg							
8		0			0		8		0							
10		0			0		10		0							
12		236			210		12		210							
16		0			0		16		0							
20		0			0		20		0							
25		0			0		25		0							
32		0			0		32		0							
Sum denne side:					210		Akkumulert sum:					210				
Samlet nettarmering denne side							Akkumulert nettarmering side 1 tom. denne side									
Diam.		Sum m2			Sum kg		Diam.		Sum kg							
K 131		0			0		K 131		0							
K 189		0			0		K 189		0							
K 257		0			0		K 257		0							
K 402		0			0		K 402		0							
Sum denne side:					0		Akkumulert sum:					0				

COWI AS							BØYELISTE				Side	2		
							Tilt.haver: Kristiansand Kommune				Oppdr.nr.		A242976	
							Oppdrag: Odderøya Barnehage				Tegn.		200	
							Utført: TFR		Dato : 22.04.2022		Kontr. TCSV		Siste rev.	
KONST.-DEL	POS NR	STÅL KVAL	DIAM. mm	ANTALL stk	KAPPL. mm	Samlet m (m²)	SKISSE MÅL I mm				ANM.	REV.		
Vegger	20	B500C	12	62	12000	744								
	21	B500C	12	128	2800	358								
	22	B500C	12	60	1500	90								
	23	B500C	25	2	4000	8								
	24	B500C	12	14	910	13								
	25	B500C			0	0								
	26	B500C			0	0								
	27	B500C	12	78	1330	104								
	28	B500C			0	0								
	29	B500C	16	4	2800	11								
Samlet armeringsmengde denne side						Akkumulert side 1 tom. denne side								
Diam.		Sum meter		Sum kg		Diam.		Sum kg						
8		0		0		8		0						
10		0		0		10		0						
12		1 309		1 162		12		1 372						
16		11		17		16		17						
20		0		0		20		0						
25		8		31		25		31						
32		0		0		32		0						
Sum denne side:				1 211		Akkumulert sum:				1 420				
Samlet nettarmering denne side						Akkumulert nettarmering side 1 tom. denne side								
Diam.		Sum m2		Sum kg		Diam.		Sum kg						
K 131		0		0		K 131		0						
K 189		0		0		K 189		0						
K 257		0		0		K 257		0						
K 335		0		0		K 335		0						
Sum denne side:				0		Akkumulert sum:				0				

COWI AS							BØYELISTE					Side	3					
							Tilt.haver: Kristiansand Kommune					Oppdr.nr.					A242976	
							Oppdrag: Odderøya Barnehage					Tegn.					200	
							Utført: TFR			Dato : 22.04.2022		Kontr. TCSV			Siste rev.			
KONST.-DEL	POS	NR	STÅL KVAL	DIAM. mm	ANTALL stk	KAPPL. mm	Samlet m (m²)	SKISSE MÅL I mm					ANM.	REV.				
Dekte		30	B500C	12	38	8175	311	8175										
		31	B500C	12	68	4370	297	4370										
		32	B500C	16	8	8175	65	8175										
		33	B500C	16	8	4370	35	4370										
		34	B500C			0	0											
		35	B500C	25	31	500	16	500										
		36	B500C			0	0											
		37	B500C			0	0											
		38	B500C	12	68	1350	92	150 600										
		39	B500C	12	38	1320	50	120 600										
Samlet armeringsmengde denne side							Akkumulert side 1 tom. denne side											
Diam.		Sum meter			Sum kg		Diam.		Sum kg									
8		0			0		8		0									
10		0			0		10		0									
12		750			666		12		2 038									
16		100			158		16		175									
20		0			0		20		0									
25		16			62		25		92									
32		0			0		32		0									
Sum denne side:					886		Akkumulert sum:					2 306						
Samlet nettarmering denne side							Akkumulert nettarmering side 1 tom. denne side											
Diam.		Sum m2			Sum kg		Diam.		Sum kg									
K 131		0			0		K 131		0									
K 189		0			0		K 189		0									
K 257		0			0		K 257		0									
K 335		0			0		K 335		0									
Sum denne side:					0		Akkumulert sum:					0						