



YARN CHARACTERISTICS

Composition	Polyethylene
Dtex	18 750 (150 000 per bundle)
Thickness	300/550 micron
Pile height	45mm
# filaments/bundle	80
Total length of tuft pile	97 mm
Pile weight	1450 g/m ²
Colour	Field green/ Lime green
Structure	Monofilament

BACKING CHARACTERISTICS

Composition	Polypropylene multilayer
Weight	220 g/ m ²
Number of perforations	90 pcs/m ²
Perforation diameter	5 mm
Coating weight	600 g/m ²
Compound base	PU

MANUFACTURED ROLLS

Roll width	400 cm
Roll length	65m or according to plan
Roll diameter	80cm

LININGS

Colour	60% white – 40% green
Width	10 cm

STANDARD

FIFA Quality/ Quality Pro

INFILL RECOMMENDATIONS, SHOCK PAD

Sand	19kg/ m ²	13 mm
Sand type	Siliceous, round, washed and dried	
Sand size	0,3 – 1,5 mm	
Rubber	8 kg/m ²	15 mm
Rubber type	Thermoplastic	
Rubber size	1,0– 2,5 mm	
Shock pad type	PU foam	
Shock pad thickness	10 mm	

PRODUCT CHARACTERISTICS

Bundle distance length	15 mm
Bundle distance width	10 mm
Production method	MTRX (3+1)
Stitches / m²	7560
Piles / m²	15 120
Filaments / m²	151 200
Total weight/ m²	2270 g



Saltex Oy, in accordance with its policy of development, reserves the right to alter above specifications without prior notice.

All measurements are + or – within 10 %.

The recommended quantities of the infill materials can be varied according to their characteristics.

We suggest to check them always by preliminary tests.