

Prinsippskisse veifundament grusvei

	asfalt AGB 11 (ca. 4 cm+3cm)
	avretting 0-32 mm veigrus (ca.15cm)
	Tensar TriAx 150
	fiberduk (kun nødvendig hvis masser i eksisterende fundament inneholder mye finstoff)
	eksisterende veifundament avrettet