

LEO A/I



Part number	05057794
Lampholder:	E40
Wattage:	1x400 W
Finish:	GR-94 / Metallic grey / Textured
Insulation class:	I
Degree of protection:	IP 65
IK-J-xxIP:	IK09 15J xx7
Power factor:	COS ϕ $\geq$ 0,9
Optic:	ASYMMETRIC INTENSIVE REFLECTOR




Description


Discharge lamp floodlight for indoor and outdoor lighting, comprising:

- Polyester powder coated die-cast aluminium housing
- Flat tempered glass diffuser
- Polished aluminium asymmetrical reflector
- Gaskets made of silicone foam directly applied on glass without joints
- Cable gland M20x1.5 for cables Ø 10- Ø 14 mm
- Stainless steel external screws
- Fully integrated stainless steel aluminium spring clips
- Powder coated steel bracket

PHOTOMETRIC DATA



TECHNICAL DRAWINGS





14018220

Frosted glass supplement to be ordered together with the fitting for factory fitted option.



14009594

External steel cowl painted aluminium grey.

Metallic grey



14001699

LEO mounting bracket in stainless steel.

Stainless steel



14012294

Steel 'U' bolt clamp for Ø60-80mm poles painted aluminium grey.

Metallic grey



14009994

Single aluminium pole top bracket for Ø60-76mm poles painted aluminium grey.

Metallic grey



14009794

External steel anti-glare louvre painted aluminium grey.

Metallic grey



14327933

Steel wire guard (20Joule).



14009694

Long bracket for ceiling mounting, painted aluminium grey.

Metallic grey



14011594

1000mm extension arm in heavy gauge steel painted aluminium grey.

Metallic grey



14010094

Twin aluminium pole top bracket for Ø60-76mm poles painted aluminium grey.

Metallic grey